



June 4, 2018

To: All Proponents

Subject: **ADDENDUM No. 1, CONTRACT 2018-002**

**Culvert Replacement – Various Locations, Township of Perry**

---

The following information, amendments and revisions shall constitute Addendum No. 1. – June 4, 2018 and shall form an integral part of the Tender Documents and where applicable, shall supersede requirements of other Tender Documents.

**1. QUESTION 1 – ITEMIZED BID LIST**

**Question:** Under which Item in the itemized Bid List Should actual installation of the culvert be placed?

**Answer:** A revised Itemized Bid List is attached and separate line items 16A, 16B, 16C have been identified for the installation of the culverts.

**DELETE** Itemized Bid List and replace with **REVISED ITEMIZED BID LIST** attached.

Part “C” Specifications Special Provisions – Tender Items has had the following added at the end of the section:

***Installation of Supplied Culverts***

***Item No. 16 A,B,C***

*To provide all labour, fuel, equipment and materials necessary to perform the work on culverts, all in accordance with the Tender documents.*

**2. QUESTION 2 – OLD GOVERNMENT ROAD CULVERT ADJACENT TO PIPELINE**

**Question:** Will the Township give an allowance for an extra to cover the requirements of the Trans Canada Pipeline as it appears the pipe is within their buffer zone?

**Answer:** The Township is in the process of contacting the Pipeline representatives to obtain further information on requirements and will provide information once obtained.

**3. QUESTION 3 – FROST TAPERS ON CULVERTS**

**Question:** Will existing frost tappers be acceptable to remain or will they need to be replaced?

**Answer:** Existing frost tappers will be acceptable to remain provided they generally meet the general standard of about 10 to 1 of low frost susceptible material.

**4. QUESTION 4 – LENGTH OF SUPPLIED CULVERTS**

**Question:** What are the lengths of each supplied culvert?

**Answer:** The approximate length of the supplied culverts are as follows:

Deer Lake Road culverts: 16 meters each

Halls Road: 10 meters each

Old Government: South culvert 9.5 meters

North culvert 11 meters.

**End of Addendum No. 1**

Yours truly,



Kim Seguin

Treasurer Township of Perry

cc: All Bidders

Addendum #1  
Contract 2018-002

**Part “B” Form of Tender Schedule of Prices**

**REVISED Itemized Bid for Contract No.  
 2018-02**

In accordance with Tender: 2018-02, the following unit prices have been used to arrive at the total contract price:

<b>Item No.</b>	<b>OPSS Spec. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total</b>
1	201	Mobilization and Demobilization.	L.S.	1		
2	706	Traffic Control	L.S	1		
3	577, 805	Environmental Protection Including Erosion and Sediment Control, Moving Water Away from Sensitive Areas	L.S.	1		
4		Removal of Existing Culverts	EA	7		
5	OPSD 219.200 Nov 2015, 805 Nov 2015	Bypass Culvert/Coffer Dam				
6	201, 180 MUNI	Clearing and Grubbing	EA	7		
7	518, 206 MUNI, 180 MUNI	Excavation Grading Including Dewatering and Sediment Control, Work Site Isolation	EA	7		
8	314 Muni	Granular Materials Granular “B” Type 1 Subgrade Backfill Suitable existing materials shall be salvaged for reuse as back fill.	TE	300		

9	314 Muni 401 Muni	Granular Materials Granular "A" Bedding, Culvert and Road Surface, Bypass staging. Suitable existing materials shall be salvaged for reuse	TE	500		
10	511	Slope Restoration Rip Rap 6" Placed with Geotextile at 600mm Depth OPSD 810.010 Nov2013 River Rock	M2	150		
11	804 Muni	Grass Seed and Cover Slope Protection and Exposed Earth. Each Culvert Location	EA	6		
12	492	Site Clean Up and Restorations	EA	6		
13		Contingency Item: Dewatering Trap OPSD 219.40 Nov2105	EA	TBD		
14		Contingency Item: Dewatering Trap OPSD 219.110 Nov2105	EA	TBD		
15		Contingency Item: Geotextile Sediment Bag Dewatering System	EA	TBD		
16A	OPSS 421 MUNI Nov 2015 OPSD 803.030 Nov 2015 OPSD 802.010 Nov 2014	Installation of supplied 600mm Plastic Culverts Locations: 27 Old Government Road 157 Old Government Road	EA	2		
16B	OPSS 421 MUNI Nov 2015 OPSD 802.030 Nov 2015 OPSD 802.031 Nov 2015	Installation of supplied two 1500mm culverts Location: 365 Halls Road	EA	2		

16C	OPSS 421 MUNI Nov 2015 OPSD 802.050 Nov 2015 OPSD 802.031 Nov 2015	Installation of supplied two Steel Elliptical Culverts at 2130mm x 1400mm each Location:1308 Deer Lake Road	EA	2		
SP - Special Provisions OPSS - Ontario Provincial Standard Specs. OPSD- Ontario Provincial Standard Drawing.					<b>Sub-Total</b>	\$ _____
					<b>HST</b>	\$ _____
					<b>Total</b>	\$ _____

Granular B material is available in the bank at no additional charge to the Contractor at the Township Bland Line Pit. Contractor shall include cost to load from bank, haul and place material.

**Rip Rap**

**Item No. 10**

The square metre price bid for this item shall include all labour, equipment and material to install rounded river rock as required under the Contract. River rock at the inlet and outlet of the bypass culvert.

Rip Rap material is available in stockpiles at no additional charge to the Contractor at the Township Old Government Road Pit. Contractor shall include cost to load, haul and place material.

**Slope Restoration/Site Cleanup**

**Item No. 11/12**

This item shall be covered on item 11 for each new culvert. This item shall include all labour, equipment and material to place minimum 50 mm of top soil, grass seed placed on graded slopes. All slopes to be graded to match adjacent ground.

Top Soil is available in stockpiles at no additional charge to the Contractor at the Township Old Government Road Pit. Contractor shall include cost to load, haul and place material.

Grass Seed is available at no additional charge to the Contractor at the Township Old Government Road Pit. Contractor shall include cost to load, haul and place material.

**Installation of Supplied Culverts**

**Item No. 16 A,B,C**

To provide all labour, fuel, equipment and materials necessary to perform the work on culverts, all in accordance with the Tender documents.

General Conditions

OPS General Conditions

April 2010

The General Conditions have not been reproduced as part of these Contract Documents.

It is the Contractor's responsibility to obtain a current copy of  
OPS General Conditions, April 2010