



June 8, 2018

To: All Proponents

Subject: **ADDENDUM No. 2, CONTRACT 2018-002**

Culvert Replacement – Various Locations, Township of Perry

The following information, amendments and revisions shall constitute Addendum No. 2. – June 8, 2018 and shall form an integral part of the Tender Documents and where applicable, shall supersede requirements of other Tender Documents.

1. QUESTION – OLD GOVERNMENT ROAD CULVERT ADJACENT TO PIPELINE

This question was included in Addendum 1, further information was being gathered and has been obtained

Question: Will the Township give an allowance for an extra to cover the requirements of the Trans Canada Pipeline as it appears the pipe is within their buffer zone?

Answer: The Culvert at 157 Old Government Road is removed from Tender 2018-002.

2. ADDITION – TO TENDER 2018-002

The Township is requesting the contractor to provide an hourly rate for excavator and operator to assist the Township forces for the removal and installation of culvert at 157 Old Government Road and other work as required. Excavator minimum requirement of 15 Ton.

REVISED PART “B” SCHEDULE OF PRICES AND ITEMIZED BID FOR CONTRACT 2018-002 ATTACHED.

End of Addendum No. 2

Yours truly,

Kim Seguin
Treasurer Township of Perry

REVISED Part "B" Form of Tender Schedule of Prices

In accordance with Tender: 2018-02, the Contractor hereby offers to complete the work specified for the following prices:

Item	Description	OPSS Spec.	Total Price (From Detailed Bid Sheets)
A	To provide all labour, fuel, equipment and materials necessary to perform the work on culverts, all in accordance with the Tender documents. Replace One Steel Corrugated Steel Culvert with a 600mm Plastic Culvert Location: 27 Old Government Road Lat: 45.528192, Lon-79.327469,	OPSS 421 MUNI Nov 2015 OPSD 803.030 Nov 2015 OPSD 802.010 Nov 2014	\$ _____
B	To provide all labour, fuel, equipment and materials necessary to perform the work on culverts, all in accordance with the Tender documents. Replace Twin Corrugated Steel Culverts with two 1500mm culverts Location: 365 Halls Road Lat:45.531959, Lon: -79.257041	OPSS 421 MUNI Nov 2015 OPSD 802.030 Nov 2015 OPSD 802.031 Nov 2015	\$ _____
C	To provide all labour, fuel, equipment and materials necessary to perform the work on culvert, all in accordance with the Tender documents. Replace 3 Corrugated Steel Culverts (1200mm, 1500mm, 1500mm) with 2 Steel Elliptical Culverts at 2130mm x 1400mm each Location:1308 Deer Lake Road Lat:45.570893, Lon:-79.284549	OPSS 421 MUNI Nov 2015 OPSD 802.050 Nov 2015 OPSD 802.031 Nov 2015	\$ _____
Subtotal			\$
13% HST			\$
HST # _____			
Total Tender Amount			\$

Hourly rate for Excavator (15 ton minimum) with Operator \$ _____ per hour

Part "B" Form of Tender Schedule of Prices

**REVISED Itemized Bid for Contract No.
 2018-02**

In accordance with Tender: 2018-02, the following unit prices have been used to arrive at the total contract price:

Item No.	OPSS Spec. No.	Description	Unit	Quantity	Unit Price	Total
1	201	Mobilization and Demobilization.	L.S.	1		
2	706	Traffic Control	L.S	1		
3	577, 805	Environmental Protection Including Erosion and Sediment Control, Moving Water Away from Sensitive Areas	L.S.	1		
4		Removal of Existing Culverts	EA	6		
5	OPSD 219.200 Nov 2015, 805 Nov 2015	Bypass Culvert/Coffer Dam				
6	201, 180 MUNI	Clearing and Grubbing	EA	6		
7	518, 206 MUNI, 180 MUNI	Excavation Grading Including Dewatering and Sediment Control, Work Site Isolation	EA	6		
8	314 Muni	Granular Materials Granular "B" Type 1 Subgrade Backfill Suitable existing materials shall be salvaged for reuse as back fill.	TE	300		

9	314 Muni 401 Muni	Granular Materials Granular "A" Bedding, Culvert and Road Surface, Bypass staging. Suitable existing materials shall be salvaged for reuse	TE	500		
10	511	Slope Restoration Rip Rap 6" Placed with Geotextile at 600mm Depth OPSD 810.010 Nov2013 River Rock	M2	150		
11	804 Muni	Grass Seed and Cover Slope Protection and Exposed Earth. Each Culvert Location	EA	5		
12	492	Site Clean Up and Restorations	EA	5		
13		Contingency Item: Dewatering Trap OPSD 219.40 Nov2105	EA	TBD		
14		Contingency Item: Dewatering Trap OPSD 219.110 Nov2105	EA	TBD		
15		Contingency Item: Geotextile Sediment Bag Dewatering System	EA	TBD		
16A	OPSS 421 MUNI Nov 2015 OPSD 803.030 Nov 2015 OPSD 802.010 Nov 2014	Installation of supplied 600mm Plastic Culverts Locations: 27 Old Government Road	EA	1		
16B	OPSS 421 MUNI Nov 2015 OPSD 802.030 Nov 2015 OPSD 802.031 Nov 2015	Installation of supplied two 1500mm culverts Location: 365 Halls Road	EA	2		

16C	OPSS 421 MUNI Nov 2015 OPSD 802.050 Nov 2015 OPSD 802.031 Nov 2015	Installation of supplied two Steel Elliptical Culverts at 2130mm x 1400mm each Location:1308 Deer Lake Road	EA	2		
SP - Special Provisions OPSS - Ontario Provincial Standard Specs. OPSD- Ontario Provincial Standard Drawing.					Sub-Total	\$ _____
					HST	\$ _____
					Total	\$ _____